NOTES

II EXISTING BOULDERS TO BE RELOCATED ON SITE.

LEGEND

- (N) TREE
- (E) TREE TO REMAIN
- (E) TREE TO BE REMOVED
- RELOCATED BOULDER
- (N) DOG WASH STATION

PICNIC TABLE   BENCH
- FURNITURE
- (E) FENCE
- (N) FENCE
- PROPOSED 6-INCH CONTOUR LINES
- (N) LIGHTING
- ADD ALT. CULVERT PIPE PLAY FEATURE
- (E) FENCE TO BE REMOVED

- CONCRETE PAVING TYPE 1 NATURAL GRAY, MEDIUM SANDBLAST FINISH
- CONCRETE PAVING TYPE 2
- STABILIZED DECOMPOSED GRANITE
- PLANTING
- SYNTHETIC TURF

New Asphalt Parking Lot

New 6-ft High Chain Link Fence

New Dog Wash Station

Remove Existing Gate and Fence

Existing Shade Structure with Seating

Existing Restroom

Maintenance Yard

Existing Drinking Fountains

New Small Dog Area Entry

Large Dog Area Entry

Existing Drinking Fountains

Entry Path

Existing Shade Structure with Seating

Remove Existing Gate and Fence

RAIL ROAD TRACKS

REED STREET

Add Alternative 15-inch High Seat Wall

Synthetic Turf

Add Alternative 15-inch High Seat Wall

Mound

SMALL DOG AREA

Mound

LARGE DOG AREA

Mound

LIMIT OF PROJECT

LAFAYETTE STREET

0 10' 20'   40'   60'   80'
(1" = 20' AT ORIGINAL SCALE (22" x 34" SHEET SIZE))

SCHEMATIC DESIGN FOR
RAYMOND G GAMMA
DOG PARK

Dillingham Associates
Landscape Architects

CHECKED BY
DESIGNED BY
DRAWN BY

No.	DATE	BY	REFERENCE

Option 'B'

PROJECT NO.

SCALE   SHEET NO.

DATE
3 / 5 / 2019   OF